

## **Fleetwood Pace Arrow 37A**

### **To Start:**

- Put key in ignition
- Start engine and let idle for a couple of minutes
- Be sure hydraulic levels are raised and turned off
- Pull lever to remove parking brake

### **Nightly Setup:**

- Park, set parking brake, keep the key in the ignition, turned to on (non-running)
- Turn on hydraulics with push buttons; use the little square level from the kitchen
- Use the buttons for hydraulics and adjust until level (if unable use level blocks inside bay and place under the jacks that need the support)
- Make sure there is nothing inside that would prevent the slides from being pushed out
- Do walk around to make sure there are no objects with in 6' of slides
- Hook up sewer (leave closed until you want to dump tanks)
- Hook up water (make sure pressure equalizer is in the line from city water)
- Do not leave water connected if temperature drops below freezing at night
- You can turn on electric water heater if needed (switch above sink next to microwave)
- Hook up power (this is a 30 amp system)
- Extend all slides after all hook ups are complete, switches are located in hallway
- Remove key from ignition
- Set all shades and front curtain
- Extend TV satellite (if needed)

### **Departure Check list:**

- All supplies stored and put away
- All storage bins closed and locked in place
- Sink Boards and stove boards in place
- Microwave off and closed
- TV satellite retracted (line up the little triangle prior to retraction)
- Electric water heater off
- Drawers next to bedroom closet closed and latched (very important prior to retracting)
- Bedroom slide will break drawers if not latched properly)
- Closet doors pinned and secured
- Ceiling vents closed (both kitchen and bathroom)
- Electric water heater off
- Awnings retracted
- Slides retracted (be sure NOTHING is in the way and chaise lounge chair is facing forward)
- Note: make sure the slides are completely retracted during your walk around, if they are not, extend them a couple of inches and retract again.
- Chairs secured
- Close and secure bedroom door for travel
- Sewer lined drained, flushed, and stored (Always dump the large line first)
- Power chord coiled and put away
- Water line disconnected after filling the domestic tank and stored

All Cargo doors latched and locked  
Start engine per startup section  
Turn on the leveling system and hit retract button  
Wait for the buzzer to go off indicating jacks have been stored  
(If light is still beeping) Do another walk around to see that all is secured for travel

**The Electrical System:**

**You can check battery voltage in the hallway**

Water pump should be shut off when not in use.

Water heater light will turn on when the propane is switched on then the light will go out, but it keeps working.

You can only run **ONE AC UNIT** when using the generator

The generator should be used when the battery indication shows low.

The batteries will charge as you travel as long as you are not using the AC. If the AC is in use while traveling then the generator should be on.

The inverter is used to run a 110 volt system without the generator on.

**The generator should not be running while connected to shore power, it will blow the generator breaker.**

The Breaker box is located in the bedroom opposite side of the TV and Bed

**Sewer System:**

**You can check levels in the hallway**

This system holds 58 gallons of gray water, and 42 gallons of black water. Gray is from the showers and sinks, and the black is from the commode. When draining, always pull the large valve first; wait to drain, then the small valve. This allows the gray water to flush the lines. Leave valves closed until dumping lines.

I have received a copy of the above Users Checklist and received a walk through of all the features by an Owner representative:

**Customer Name:**

**Date:**

---

**Representative:**

**Date:**

---